



LEGEND

- WETLAND
- PERMANENT WETLAND IMPACTS
- PERMANENT WETLAND BUFFER IMPACTS
- TEMPORARY WETLAND BUFFER IMPACTS
- WETLAND BUFFER RESTORATION
- WETLAND BUFFER ENHANCEMENT

WETLAND BOUNDARY DELINEATED
 WETLAND BOUNDARY APPROXIMATE
 WETLAND BUFFER BOUNDARY

IMPACTS/MITIGATION	TOTAL AREA SQ. FT.
PERMANENT WETLAND IMPACTS	1,178
PERMANENT WETLAND BUFFER IMPACTS	13,950
TEMPORARY WETLAND BUFFER IMPACTS	4,168
WETLAND BUFFER RESTORATION	4,168
WETLAND BUFFER ENHANCEMENT	15,528

PLANTING NOTES:

1. PLANTING SHALL OCCUR DURING THE DORMANT SEASON (11/1-2/28). PLANTING MAY BE ALLOWED AT OTHER TIMES AFTER REVIEW AND WRITTEN APPROVAL BY THE ENGINEER IN COORDINATION WITH THE PROJECT ENVIRONMENTAL SCIENTIST OR LANDSCAPE ARCHITECT.
2. COMPACTING SOIL IN THE PLANTING AREAS OR WETLAND AREAS TO BE PROTECTED SHALL BE AVOIDED, MINIMIZED AND MITIGATED.
3. PLANTS SHALL BE PLANTED IN A RANDOM INTERMIXED LAYOUT WITH TRIANGULAR SPACING AT THE SPACING INDICATED IN THE PLANTING SCHEDULE.
4. APPLY A 3" LAYER OF WOOD CHIPS MULCH TO PLANTING AREAS.
5. ANY DISCREPANCIES WITH THE PLANS AND/OR THE SPECS AND/OR THE SITE CONDITIONS SHALL BE BROUGHT TO THE ATTENTION OF THE KING COUNTY INSPECTOR PRIOR TO PROCEEDING WITH CONSTRUCTION.
6. PROVIDE EROSION CONTROL AS NEEDED FOR STABILIZING THE PLANTED AREAS.
7. MEET AND MATCH EXISTING GRADES WITH SMOOTH TRANSITIONS.
8. WITHIN ALL DISTURBED AREAS TO BE PLANTED OR SEEDED, PROVIDE OR INSTALL TOPSOIL TYPE A TO THE DEPTH SPECIFIED. TOPSOIL SHALL BE CULTIVATED INTO THE SUBGRADE AS SPECIFIED.
9. INSTALL HIGH VISIBILITY FENCING AROUND WETLAND BUFFER ENHANCEMENT AREAS. FENCING IS TO REMAIN IN PLACE THROUGHOUT PLANT ESTABLISHMENT AND PERMIT MONITORING REQUIREMENTS.
10. PLANT QUANTITIES ARE PROVIDED FOR CONTRACTOR CONVENIENCE. CONTRACTOR IS RESPONSIBLE TO INSTALL PLANT MATERIAL QUANTITIES BASED ON THE SPACING LISTED. CONTRACTOR SHALL VERIFY PLANT MATERIAL QUANTITIES PRIOR TO PURCHASING PLANT MATERIAL.
11. ANY AREAS DISTURBED BY CONSTRUCTION AND NOT SHOWN TO BE REVEGETATED ON THESE PLANS SHALL BE RESTORED AND SEEDED AT A MINIMUM.

MERIDIAN
W.S.L.G.N.Z.

HORIZONTAL DATUM:
WASHINGTON STATE PLANE
NORTH ZONE NAD '83/91
BASED UPON KING COUNTY
SURVEY CONTROL.

VERTICAL DATUM:
NAVD 1988 BASED UPON KING
COUNTY SURVEY CONTROL



Know what's below.
Call before you dig.

SURVEY JOB No.:	17042	05/2019
CHECKED:	T. CRAY	05/2019
CAD ENTERED:	VERDUGO/PARRETT	2/14/22
DESIGNED:	A. VERDUGO	2/14/22
CHECKED:	M. KARINEN	2/14/22
SUPERVISOR:	A. MCMANUS	2/14/22

NUM.	REVISION	BY	DATE

**90% DESIGN
PROGRESS COPY
03/03/22**

FED. AID No. _____

PROJECT No. 1131235

MAINTENANCE DIVISION No. 4

KING COUNTY DEPT. OF LOCAL SERVICES
JOHN TAYLOR, DIRECTOR
**S 360th ST AND MILITARY RD S
ROUNDBOUT**

WETLAND IMPACTS AND MITIGATION

SHEET
64
OF
63
SHEETS

320-93 (64)