

# 2020 Decennial Flow Monitoring & Data Finalization

Presented to MWPAAC  
Engineering and Planning Subcommittee  
October 6, 2022



**King County**


Department of Natural Resources and Parks  
**Wastewater Treatment Division**

# Presentation Overview

- Project Objective
- 2020 Decennial Flow Monitoring (DFM) Approach
- Site Locations
- Equipment
- Data Review
- Data Finalization
- Current Status
- Conveyance System Improvement Plan

# Monitoring Approach

- 2000 – 2002 I/I Project deployed meters at the Mini Basin level
- 2010 DFM deployed meters at the Modeling Basin level
- 2020 DFM – Deploy meters at the Modeling Basin level, primarily in King County Wastewater Treatment Division pipes




# Goals of 2020 DFM Monitoring Approach

- Maintain existing sewer model basins and update for growth and changes in local systems
- Install meters to monitor:
  - areas primarily new construction/development
  - high priority CSI needs
  - project areas in CIP plan
- Leverage existing sewer model to assess meter locations

# 2020 DFM Site Locations

- 132 sites
- [Interactive Map](https://bit.ly/3Cmc9Zw)  
(<https://bit.ly/3Cmc9Zw>)




# Site Investigations

- Look out for...
  - Safety/Accessibility
  - Laminar flow
  - Bends in pipe
  - Inputs
  - Silt/Sediment
  - Evidence of surcharging
- Auto fail conditions:
  - Negative or stagnant velocity
  - Inputs that affect hydraulics
  - Inaccessible or unsafe
  - Site is surcharge in dry conditions


# Equipment – ADS Triton+



## Smart Depth Ultrasonic Sensor



## Peak Combo Sensor



# ADS Triton+ Installation



Smart Depth  
Ultrasonic  
Sensor



Peak Combo  
(Ultrasonic, Velocity  
and Pressure) Sensor





# Equipment - HACH




HACH Flo-Dar

Area Velocity Sensor




In-pipe Ultrasonic Sensor

# HACH Flo-Dar



# Typical HACH Flo-Dar Installation



# Flow Data Reviews

- Review data twice a week
- Maintenance requests twice a week
- Battery issues
- Communication issues
- Bad depth/velocity (flat lining, erroneous data, drifting)
- Missing data/data gaps
- Incorrect programming


# Hydrograph

RVISTAW314-35\mp1\RAWVEL

Depth Confirmations

RVISTAW314-35\mp1\UNIDDEPTH

Velocity Confirmations




Peak Velocity (fps)

Ultrasonic depth (in)

Flow (MGD)

# Hydrograph with Verifications

Pipe Height: 18.00




Peak Velocity (fps)

Ultrasonic depth (in)


Flow (MGD)

# Diurnal Flow Pattern



Diurnal flow for each day of the week.

# Scatter graph





# Flow Data Finalization Elements

- $Q=vA$
- Pipe Dimensions
- Accurate depth
- Accurate velocity

Installation Generator - BORG\_RG2\mp1

File Edit Help

Configuration

Select Installation: Elliptical (35.50 in H, 36.00 in W)

Installation: Pipe Type: Elliptical

Dimensions/Parameters

Height: 35.5 in Width: 36 in

Quantity Coefficients

VGain: 0 HC: 0 Silt: 0 in

Slope: 0 Roughness: 0 in

Friction Factor: Camp's Curve Average to Peak: 0.90

Installation Table

	DEPTH (in)	AREA (sqft)	PERIM (ft)	CHORD (ft)	QMANING (MGD)	QCOLEBRO OK (MGD)	QWEIR (MGD)	QFLUME (MGD)	QLOOKUP (MGD)
1	0.000000	0.000000	0.000000	0.000000	0.000000	0.000000	0.000000	0.000000	0.000000
2	0.138672	0.002886	0.379564	0.374267	0.000000	0.000000	0.000000	0.000000	0.000000
3	0.277344	0.008152	0.535416	0.528254	0.000000	0.000000	0.000000	0.000000	0.000000
4	0.416016	0.014959	0.655218	0.645702	0.000000	0.000000	0.000000	0.000000	0.000000
5	0.554688	0.023003	0.756396	0.744118	0.000000	0.000000	0.000000	0.000000	0.000000

Pipe Table


# Data Finalization and Verifications

- Verifications of flow meters
  - Manual depth
  - Hand-held velocity meter
  - Velocity Profiles
- Performed periodically
  - At installation
  - "2 weeks" after installation
  - Dry and wet seasons
  - At removal



# Flow Velocity Verification

- Flows > 6 inches measured using a portable velocity meter
- Low flow (usually < 1 to 2 inches of DOF) measured using Propeller Meter




## *Average to Peak Ratio K*

$$= 1.9 \text{ fps} / 2.1 \text{ fps} = 0.9$$

- slow flow near pipe wall (friction)
- fastest flow near surface and near center
- velocity profile measured by a grid of point velocity measurements


# Velocity Profiles

## Typical Velocity Profile (feet per second)




# Upstream / Downstream


- Data Analysts to perform upstream / downstream comparison where applicable in the system



# Data Review & Finalization Process




# Current Status



- Closeout Phase of project
- Began removals in May 2022, finished September 2022
- 54 removed
- 78 sites of 132 installed sites remain in

# Conveyance System Improvement (CSI) Program


- DFM is part of the CSI Program
- Conveyance policies call for monitoring coincident with the Census
- Flow monitoring data will inform model calibration and update of planning assumptions





# Update Planning Assumptions for Wastewater Flow Forecasting in 2023-24

- Planning horizon
- Model basin and service area delineation
- Future population
- Sewered areas growth rate
- Water consumption
- Water conservation
- Degradation I/I
- New construction I/I



2014 Report available in CSI Program Library:

<https://kingcounty.gov/services/environment/wastewater/csi/library.aspx>

# Questions?

Jenny Ho, 2020 Decennial Flow Monitoring Project Manager

[Jenny.Ho@kingcounty.gov](mailto:Jenny.Ho@kingcounty.gov)

Nicole Smith, Conveyance System Improvement Program Manager

[Nicole.Smith@kingcounty.gov](mailto:Nicole.Smith@kingcounty.gov)