

Technical Information Meeting April 24, 2017





Presentation agenda

- Welcome and introductions
- Project overview and final alignment
- HDD construction
- Pipe rehabilitation
- Easement process
- Next steps



Project alignment



1612_8137a_NML_enatai_mapONLY_for_NWSLTR.ai



Construction methods

- Open-cut
- In-water
- Trenchless (Horizontal Directional Drilling)
- Pipe rehabilitation Cured In Place Pipe CIPP



1612_8137a_NMI_enatai_mapONLY_for_NWSLTR.ai



HDD process

Three main steps:

- Pilot bore
- Reaming pass
- Pipe pullback



Not to scale



Typical Horizontal Directional Drilling





Enatai HDD – used in areas where pipe is too deep to be installed by open cut





Protecting the Piles and Upper Soil Layer







48-inch Conductor Casing







Ving County Department of Natural Resources and Parks Wastewater Treatment Division

NORTH MERCER ISLAND/ENATAI Sewer Upgrade Project

HDD Process Step 1: Pilot bore



- Drill from Enatai Beach Park toward Sweyolocken
- 12-inch diameter hole
- Drill about 200 feet per day







HDD process: Step Two – Reaming pass





- Pull reamers from Sweyolocken to Enatai Beach Park
- Enlarge the hole from 12 inches to 48 inches
 - Several Passes (12 to 24); (24 to 36); (36 to 48)
- Takes about 30 days (10 days per pass)









NORTH MERCER ISLAND/ENATAI Sewer Upgrade Project HDD process: Step <u>3</u>: Pipe pullback

- Pipe pulled through the bore
 - Enatai Beach Park to Sweylocken
- Sections of pipe floated in Lake Washington to the bore entry
- Large cranes on barges
 - lift pipe to insert in the borehole
- Drilling Equipment
 - at both ends of the bore
- Takes Approximately 2-3 days
 - (including set up and pull)







¹⁶¹²_8137a_NML_enatai_mapONLY_for_NWSLTR..ai



Pipe Rehabilitation

Existing North Mercer Island/Enatai Sewer:

- Rehabilitated
- Remain in service
 - By-Pass sections for rehabilitation
- Receive flows
 - 25 homes
 - 2 City of Bellevue sewers





Portion of the Rehabilitation Impacting residents





Pipe Rehabilitation

- Crews at manhole locations will install a new liner that will be cured in place (called CIPP)
- Some of this work will be conducted from the water







Step 1: Insert Liner in Pipe And Inflate Liner



Step 3: Run UV Light Train Down Pipe to Cure Liner



Step 2: Prepare the UV Light Train



Step 4: Completed New Structural Pipeline



NORTH MERCER ISLAND/ENATAI Sewer Upgrade Project Rehabilitation Access

- PROCESS:
 - Clean Sewer
 - Insert Liner
 - Cure Liner
 - Reinstate Services
- WATER ACCESS:
 - 80-ft x 30-ft barge for liner insertion
 - 50-ft x 25-ft barge for curing equipment
- ACCESS FROM LAND:
 - Liner Truck
 - Video Truck
 - Air Compressor
 - Winch



Easement process

- 1. Contact from King County *occurred in January* 2017
- 2. County orders property title reports
- 3. County determines square footage needs
- 4. County hires independent appraiser and verifies with second independent appraiser



Easement process continued

- 5. King County presents appraised value and easement document, and meets with you to answer questions
- 6. If needed, County explains original appraisal or provides up to \$750 toward your own appraisal
- 7. Finalize agreements





- Initial design drawings
- Confirm property easement needs
- Refine construction methods
- Begin identifying construction sequencing (when we will build what)



Next steps: Environmental Review – fall 2017



- Identify environmental impacts
- Conduct environmental review under State Environmental Policy Act (SEPA)
- Opportunity for public input



Our commitment to you

- Outreach and coordination with individual property owners
- Community group briefings
- Street walk and talks
- Gather community input where we can





Questions and comments

For more information:

- Kristine Cramer, community relations
- kristine.cramer@kingcounty.gov
- 206-477-5415